

Certificate No: CBA- 302


Issued : August 2014

Issued by Concrete Block Association

<b>Ground Floor, Insulation above slab – External wall</b>  Table K.1 Ref E5 Approved -value = 0.16 W/mK	Inner leaf	100 mm blockwork
	Cavity	Full fill insulation, see tables for options
	Outer leaf	102 mm Brick = 0.77
	Floor	100mm slab with 100 mm floor insulation = 0.022 Below a 75mm screed

#### Key Points

- 1 The R-value of the perimeter insulation should be at least  $0.8\text{m}^2\text{K/W}$
- 2 Ensure the floor insulation is tightly butted against the external wall.
- 3 Continue the cavity insulation at least 225mm below the top of the concrete.



Calculations have been performed in accordance with:  
BS EN ISO 10211:2007, BR497 and BS EN ISO 13370:2007

Calculation prepared by: Chris Sanders B.Sc, M.Sc, GCU, Cowcaddens Rd, Glasgow G4 0BA.  
For more information contact **0116 232 5165** (C.B.A)

**Calculated  $\psi$ -values and f-values with 100mm floor insulation  
 $\lambda=0.022$ , and **cavity Insulation** as highlighted**

	Inner leaf blockwork					
	Ultra lightweight		Lightweight		Dense	
<b>Cavity Insulation</b> ↓	$\psi$ -value W/mK	f-value	$\psi$ -value W/mK	f-value	$\psi$ -value W/mK	f-value
<b>100mm</b> =0.037	<b>0.060</b>	0.919	<b>0.097</b>	0.907	<b>0.159</b>	0.884
100mm =0.032	<b>0.059</b>	0.921	<b>0.097</b>	0.911	<b>0.160</b>	0.888
<b>150mm</b> =0.037	<b>0.058</b>	0.925	<b>0.097</b>	0.914	<b>0.162</b>	0.894
150mm =0.032	<b>0.057</b>	0.927	<b>0.097</b>	0.916	<b>0.164</b>	0.897

The f-value should be above 0.75 to minimise the risk of mould in dwellings.

### On-site Checklist

- Perimeter insulation with a resistance of at least 0.8 W/m<sup>2</sup>K installed
- Floor insulation is tightly butted against the external wall
- Cavity insulation continues at least 225mm below the top of the concrete

**Site manager/supervisor**.....

**Site name**.....

**Plot number**.....

**Date**.....