

**Certificate No: CBA-P8-T-B2**


**Issued : January 2016**

**Issued by Concrete Block Association**

<b>Exposed floor (Inverted)</b> Table K.1 Ref P8 Default $\psi$ -value = 0.24 W/mK	Inner leaf	100 mm blockwork
	Cavity	Partial cavity fill with low-e facing and 50mm cavity
	Outer leaf	102 mm brick $\lambda = 0.77$
	Exposed floor	Timber with 45mm wide joists on hangers over vehicle access with 150mm of insulation, $\lambda = 0.037$ , between the joists and 25mm of insulation, $\lambda = 0.022$ below the joists

**Key Point**

1. Ensure the floor insulation is tightly butted to the wall



Calculations have been performed in accordance with:  
BS EN ISO 10211:2007, BR497 and BS EN ISO 13370:2007

Calculation prepared by : Chris Sanders B.Sc, M.Sc. GCU, Cowcaddens Rd, Glasgow G4 0BA  
For more information contact 0116 232 5165 (CBA)

Calculated  $\psi$ -values and f-values for exposed floor (inverted) and **cavity insulation** as highlighted

\*The  $\psi$ -value applied to each dwelling around the junction should be allocated as follows:

- 2 dwellings – 2/3 of tabulated value to dwelling occupying 2 segments around junction and 1/3 of tabulated value to dwelling occupying 1 segment around junction
- 3 dwellings – 1/3 of tabulated value to each dwelling

**1. With lightweight blocks in the separating wall  $\lambda = 0.6$  W/mK**

Cavity Insulation	Inner leaf blockwork					
	Ultra lightweight		Lightweight		Dense	
	$\psi$ -value W/mK*	f-value	$\psi$ -value W/mK*	f-value	$\psi$ -value W/mK*	f-value
50mm $\lambda=0.022$	0.178	0.876	0.177	0.876	0.177	0.876
100mm $\lambda=0.022$	0.174	0.871	0.173	0.872	0.174	0.872

**2. With dense blocks in the separating wall  $\lambda = 1.33$  W/mK**

Cavity Insulation	Inner leaf blockwork					
	Ultra lightweight		Lightweight		Dense	
	$\psi$ -value W/mK*	f-value	$\psi$ -value W/mK*	f-value	$\psi$ -value W/mK*	f-value
50mm $\lambda=0.022$	0.266	0.863	0.265	0.863	0.265	0.863
100mm $\lambda=0.022$	0.263	0.858	0.262	0.858	0.263	0.858

The f-value should be above 0.75 to minimise the risk of mould in dwellings.

## On-site Checklist

1. Floor insulation is tightly butted to the wall

**Signed:**

**Site manager/supervisor**.....

**Site name**.....

**Plot number**.....

**Date**.....